

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of work:- Providing and filling of potholes in ward no. 07 Byatarayanapura, Kodigehalli sub division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	320.55 372.48	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications	cum	83.16	
2	320.55 363.30	KSSRB M 400-17: Providing laying, spreading and compacting graded fine aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specific	sqm	1713.96	
3	3205.50 3633.00	Filling pot holes and patch repairs with bituminous concrete 40mm. KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.30, back filling the potholes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface all as per clause	sqm	370.44 305.64	

ಕರಡು ಬಿಡುಗಡೆ ಮಾಡಲ್ಪಟ್ಟು
ಅಧ್ಯಕ್ಷರ ಸಹಿ 04 (FOUR)
ಅಧ್ಯಕ್ಷರ ಕಛೇರಿ/ಇಲಾಖೆ
ಅನುಮೋದನೆ ನೀಡಿರಲಾಗಿದೆ

23.11.16

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

7/11